BRUHAT BANGALORE MAHANAGARA PALIKE

APPROVED SCHEDULE - B

BBMP/2013-14/WS/WORK_INDENT9160

Maintenance works like Debris Clearence. Maintenance of Sholder Drain, Covering Slabs, Culverts etc.,in Ward No.06, Byatarayanapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K SUDHAKAR REDDY	
				In Figures	Rates In Words
1	2210.09	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3. Page No. 152 / Item No. 19.1/ PWD SR 2013-14	Cum	63.96	Rupees Sixty Three and Ninety Six Paise Only
2	3476.80	KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, Specification No KBS 2.1(a) / 2.3.1, No. 5 / Item No. 2.1/ PWD SR 2013-14	Cum	122.68	Rupees One Hundred Twenty Two and Sixty Eight Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92